

July 25, 2017

Dear Sir:

Attached is Addendum No. 3 dated July 25, 2017 to the Specifications for The Manitoba Water Services Board Contract No. M.W.S.B. 1368, Binscarth and Rosburn Reservoir Upgrades and New Booster Station on Road 117N. Please verify receipt of this Addendum for our records by fax to (204) 726-6290.

**\*  
ACKNOWLEDGEMENT OF RECEIPT OF ALL ADDENDUMS  
MUST BE INCLUDED IN THE TENDER SUBMISSION.**

Failure to include acknowledgement shall cause the tender to be rejected. If Tender is submitted before Addendum is issued, the Board will accept a faxed acknowledgement prior to the tender closing.

Yours truly,

R. Lytle  
Construction Manager

---

The Manitoba Water Services Board  
Unit #1A - 2010 Currie Blvd.  
Brandon, MB R7B 4E7

Dear Sir:

We have received Addendum No. 3 dated July 25, 2017 to the Specifications for The Manitoba Water Services Board Contract No. M.W.S.B. 1368, Binscarth and Rosburn Reservoir Upgrades and New Booster Station on Road 117N.

Yours truly,

---

Company

---

Per

**THE MANITOBA WATER SERVICES BOARD**

**CONTRACT NO. M.W.S.B. 1368**

**MUNICIPALITY OF RUSSELL BINSCARTH**

**BINSCARTH & ROSSBURN RESERVOIR UPGRADES  
& NEW BOOSTER STATION ON ROAD 117N**

**ADDENDUM NO. 3**

To the tender documents for the Municipality of Russell Binscarth, Binscarth & Rossburn Reservoir Upgrades and New Booster Station on Road 117N

July 25, 2017

**PRECEDENCE**

This addendum forms an integral part of the specifications describing all aspects of the work and is to be read in conjunction therewith.

**SCOPE**

The purpose of this addendum is to amend the following sections of the Tender Documents:

**1.1 STAINLESS STEEL PIPING**

- .1 Clarification:
  - .1 All stainless steel piping shall be type 304 or 316, Schedule 10, unless the drawings indicate otherwise.

**1.2 DRAWING 4866-01-E-102**

- .1 Revise tag “New Main Control Panel” to “Existing Main Control Panel”
- .2 Revise tag “New Milltronics” to “Existing Milltronics”
- .3 The above noted equipment shall remain in service until new equipment is installed and commissioned.

**1.3 DRAWING 4866-03-S-101**

- .1 Revise Section 3 - Concrete Slab
  - .1 Remove all references to “By Owner”

**END OF ADDENDUM #3**