

May 1, 2018

Dear Sir:

Attached is Addendum No. 1 dated May 1, 2018 to the Specifications for The Manitoba Water Services Board Contract No. M.W.S.B. 1418, Prairie View Municipality, Birtle Water Supply System, Reservoir & Pump House Superstructure. Please verify receipt of this Addendum for our records by fax to (204) 726-6290.



**ACKNOWLEDGEMENT OF RECEIPT OF ALL ADDENDUMS  
MUST BE INCLUDED IN THE TENDER SUBMISSION.**

Failure to include acknowledgement shall cause the tender to be rejected. If Tender is submitted before Addendum is issued, the Board will accept a faxed acknowledgement prior to the tender closing.

Yours truly,

R. Lytle  
Construction Manager

---

The Manitoba Water Services Board  
Unit #1A - 2010 Currie Blvd.  
Brandon, MB R7B 4E7

Dear Sir:

We have received Addendum No. 1 dated May 1, 2018 to the Specifications for The Manitoba Water Services Board Contract No. M.W.S.B. 1418, Prairie View Municipality, Birtle Water Supply System, Reservoir & Pump House Superstructure.

Yours truly,

---

Company

---

Per

**THE MANITOBA WATER SERVICES BOARD**

**CONTRACT NO. M.W.S.B. 1418**

**PRAIRIE VIEW MUNICIPALITY  
BIRTLE WATER SUPPLY SYSTEM**

**RESERVOIR & PUMP HOUSE SUPERSTRUCTURE**

**ADDENDUM NO. 1**

To the tender documents for the Prairie View Municipality, Birtle Water Supply System,  
Reservoir & Pump House Superstructure

May 1, 2018

**PRECEDENCE**

This addendum forms an integral part of the specifications describing all aspects of the work and is to be read in conjunction therewith.

**SCOPE**

The purpose of this addendum is to amend the following sections of the Tender Documents:

**1.1 TENDER FORM MWSB 3A**

- .1 Revised Submission Deadline: **Friday, May 11, 2018.**

**1.2 DRAWING 4977-02-A-601**

- .1 For all Doors, revise door and frame finish code to **PT1.**

**1.3 DRAWING 4977-02-D-102**

- .1 Provide the following sizes of pump column sleeves:
  - .1 5 - 350 mm diameter
  - .2 1 - 250 mm diameter
- .2 Add one (1) additional 100 mm diameter pipe penetration near intersection of gridlines 2 and D.

**1.4 DRAWING 4977-02-D-501**

- .1 Clarification of Typical Detail #2:
  - .1 Unless specifically shown otherwise on the drawings, all stainless steel floor penetration sleeves for process piping shall have plain ends terminating 250 mm from either side of floor. Flanges shall be added by others as required.
- .2 Clarification of Typical Detail #3:
  - .1 SCH40 PVC pump column sleeve shall be cast flush with the underside of the main floor slab and shall extend 750 mm above the top side. Total length per sleeve = 1.0 m.
  - .2 Flanged pump column is **by others**.
- .3 Clarification of Typical Detail #7:
  - .1 Replace description with: "Ultrasonic & Float Sleeve"

**1.5 DRAWING 4977-02-S-502**

- .1 Delete Typical Detail #5. Concrete and rebar for pump bases shall be completed by others.

**1.6 DRAWING 4977-02-M-101**

- .1 Clarification: PVC SDR35 sanitary sewer stub shall be **150 mm** diameter.

**END OF ADDENDUM #1**